



Final Report

Acknowledgements

We would like to express a heartfelt thank you to our 14 participating families who accompanied us during this adventure and remained committed throughout the entire journey.

They remained patient when unexpected technical surprises arose, and most importantly, they remained curious to learn and to contribute to this project. We are grateful for having had you on our side!

A big thank you also to our over 60 colleagues from all over Creos, as well as all project partners involved. Despite many late evenings and head scratches, they supported us with their expertise and efforts.

Creos Innovation Team

Table of contents

- Acknowledgements.....2
- Executive Summary 6
- List of abbreviations 9
- 1. Project objectives**10
- 2. Creos living lab in the context of the energy transition** 13
 - 2.1. Evolution of the loads on the low voltage grid 14
 - 2.2. Challenges for the low voltage grid 15
 - 2.3. Solutions to manage the energy transition..... 18
- 3. Selection process of participants** 19
 - 3.1. Technical pre-selection process 21
 - 3.2. Participants’ selection process 22
 - 3.2.1. Information sessions and first contact 22
 - 3.2.2. Expectations on participants 23
 - 3.2.3. Individual visits 23
 - 3.2.4. Selection criteria 23
- 4. Participants’ technical installations** 24
 - 4.1. Target configuration 26
 - 4.2. Installed assets 27
 - 4.2.1. Heat pumps 27
 - 4.2.2. PV installations 27
 - 4.2.3. Electric vehicles 28
 - 4.2.4. Wallboxes.....28
 - 4.2.5. Battery storage systems 29
 - 4.2.6. Energy meters and smart switches 29
 - 4.3. Digital tools and communication protocols 30
 - 4.3.1. Smarty+ 30
 - 4.3.2. Home Energy Management System 31
 - 4.3.3. Visual representation of communication flows with the HEMS 33
 - 4.3.4. EV application.....33
 - 4.4. Lessons learned and challenges in electrifying and digitalizing homes 33
 - 4.4.1. Physical constraints in existing installations 34

- 4.4.2. Digitalization of homes requires proper installation and maintenance 35
 - 4.4.3. Preparing the workforce for the energy transition 36
- 5. Smart grid** 37
 - 5.1. Evolution of the Electricity Network 38
 - 5.2. Creos Smart Grid Vision 39
 - 5.3. Smart Grid Tests in the Living Lab 41
 - 5.4. Smart Grid Developments for the Creos Living Lab 42
 - 5.4.1. Smart Meter Data 43
 - 5.4.2. Real-time Smarty+ Data 43
 - 5.4.3. Real-time Transformer Station Measuring Device 44
 - 5.4.4. Load Management Mechanism via Relays 44
 - 5.4.5. Digital Twin of the grid – Kopr 45
 - 5.4.6. Smart Grid Data Flows 46
 - 5.5. Outcomes from forecast-based management 48
 - 5.5.1. Summary: Suitability of Forecast-Based Load Management 49
 - 5.5.2. Quality of Consumption Forecasts 50
 - 5.5.3. Outcomes of Forecast-Based Load Management for EV Chargers 51
 - 5.5.4. Quality of Production Forecasts 52
 - 5.5.5. Outcomes of Forecast-Based Injection Load Management 54
 - 5.6. Outcomes from real-time data-based load management 55
 - 5.6.1. Summary: Suitability of Real-time Based Load Management 56
 - 5.6.2. Control Algorithms and Data used for Real-time Load Management 57
 - 5.6.3. Quality of Consumption Forecasts 58
 - 5.6.4. Results of Real-Time Consumption Load Management 59
 - 5.7. Insights on Power Line Communication for Load Management 62
 - 5.8. Insights from High Resolution LV Grid Measurements 65
- 6. Customer behaviour** 72
 - 6.1. General description of customer behaviour phases 73
 - 6.1.1. Active participation phases 74
 - 6.1.2. Passive participation phases during smart grid test phases 75
 - 6.2. Identified challenges 75

- 6.2.1. Energy literacy..... 75
 - 6.2.2. Engaging participants 76
- 6.3. Insights on consumption behaviour of different energy transition assets 77
 - 6.3.1. Heat pump consumption in winter 77
 - 6.3.2. Simultaneity of EV charging 79
- 6.4. Outcomes on reducing consumption peaks in winter with incentives on the consumption tariff . 82
 - 6.4.1. Description of the test phases 82
 - 6.4.2. Cross-phase analysis 85
 - 6.4.3. Emergency Simulation 89
- 6.5. Outcomes on reducing injection peaks in summer with incentives on the consumption tariff . 90
 - 6.5.1. PV Control Sites 91
 - 6.5.2. Evolution of consumption behavior 91
 - 6.5.3. Impact of the phase on the injection into the grid 93
- 6.6. Insights into operating home storage batteries as grid support 95
 - 6.6.1. Battery operation strategies 96
 - 6.6.2. Mitigation of injection peak in spring and summer 97
 - 6.6.3. Potential to mitigate the consumption peak in winter 98
- 7.Outofscope**.....100
- 7.1. Vehicle-to-Grid (V2G) 101
- 7.2. Load management of heat pumps 101
- 7.3. Energy communities 101
- 7.4. Testing new communication standards for the HEMS 101

Executive Summary

The energy transition is rapidly transforming low-voltage (LV) electricity grids. Electrification of mobility and heating, combined with increasing photovoltaic (PV) generation and home storage battery systems, introduces new consumption and injection peaks that challenge traditional grid operation.

The Creos Living Lab tested, under real-life conditions, how future LV grids can integrate high shares of EVs, heat pumps, PV systems and batteries while maintaining reliability and customer comfort. Over one year, 14 households simulated the “2030 household” and enabled Creos to evaluate both customer behavior incentives and smart grid load management mechanisms.

To achieve this, households were equipped with technical installations reflecting future residential electrification:

- 16 full-electric vehicles
- 12 heat pumps
- 11 PV installations
- 4 residential battery storage systems
- 14 Home Energy Management Systems (HEMS) capable of steering EV charging and battery operation

In parallel, the project implemented key elements of the future smart grid architecture at local scale:

- Real-time LV feeder measurement devices at the transformer station
- Integration of granular measurement data into Creos’ digital twin Kopr
- Forecasting algorithms for load and PV generation
- Implementation of both forecast-based and real-time load management strategies
- Interfaces enabling remote activation of smart meter relays connected to PV systems and EV chargers
- The Living Lab therefore served as a full-scale test environment for the Creos smart grid vision, delivering both operational and strategic insights for future decision making.


List of abbreviations

API	Application Programming Interface
EV	Electric Vehicle
HEMS	Home Energy Management System
HP	Heat Pump
ICT	Information and Communication Technology
LV	Low Voltage
MV	Medium Voltage
NECP	National Energy and Climate Plan
OCPP	Open Charge Point Protocol
PLC	Power Line Communication
PV	Photovoltaic installation
RES	Renewable Energy Sources
SoC	State of Charge
TAB	“Technische Anschlussbedingungen” or technical connection requirements
ToU	Time-of-Use
V2G	Vehicle-to-Grid

1 Project objectives

The energy transition is reshaping how we produce and consume electricity. With the rapid expansion of decentralized energy sources such as solar panels and the growing popularity of heat pumps and electric vehicles, our electricity grids are being pushed to their limits. These changes are exciting but also bring new challenges. How can we ensure our grids keep up with this transformation? How can customers with their everyday devices like EV chargers and heat pumps support the stability of the grid? And how can smart technologies help integrate these innovations without compromising the quality and reliability of electricity supply?

The Creos Living Lab is designed to find answers. Set in a real-life neighbourhood, this pilot project tests and demonstrates how the energy transition can align with Luxembourg’s ambitious climate goals while preserving comfort and ensuring a reliable electricity supply.



By combining innovative technologies with active community involvement, the Creos Living Lab demonstrates how the energy transition can work in harmony with everyday life. It's not just about managing challenges—it's about turning them into opportunities for a cleaner, smarter energy future.




Figure 1
Future smart household

2 Creos Living Lab in the context of the energy transition

The Luxembourgish National Energy and Climate Plan (NECP) has set the goals and the pathway for the country's decarbonization. To achieve these goals, the Luxembourgish government prioritizes technologies such as heat pumps and electric mobility which achieve higher energy efficiencies via electrification. These additional loads will have a major impact on the electricity grid, affecting both high voltage levels, such as the interconnection with neighbouring countries, and low voltage levels, meaning the distribution grid to which residential houses are connected.

2.1

Evolution of the loads on the low voltage grid

Historically, the loads in the low voltage levels were characterized by consumption peaks at noon and in the early evening hours, when residents were at home. The typical peaks for these historical customers are around 4 to 6 kW, which are mainly for cooking, washing and entertainment.




Figure 2a
Example of a load profile of a historical household consumer.
The evening consumption peak is usually between 17 and 21h.




Figure 2b
Example of a load profile of a typical 2030 household prosumer in Winter, with the household consumption and the generation profile of a PV installation.




Figure 2c
Example of a load profile of a typical 2030 household prosumer in Summer, with the household consumption and the generation profile of a PV installation.

3

Selection process of participants

The selection of the location of the Creos Living Lab was a key preparatory step, as the project's success depends on participants' collaboration and motivation.


The objective was to identify a single street based on technical and motivational criteria:

Technical criteria

narrowed down a restricted set of eligible streets.

Motivational criteria

guided the final selection, including participants’ openness and patience toward emerging technologies, as a pilot project entails that some technologies might not be at full maturity yet.



Key factors contributing to the success of this selection phase included support from an external communication expert, the creation of a visual identity and engaging materials (flyers, rollouts), and collaboration with municipalities and project partners. These factors enhanced the credibility and professionalism of the initiative.

Table 1
Timeline of the selection process phases up until the project launch

3.2.2

Expectations on participants

During the project, participants are expected to:

- Be available for the installation of technical equipment, such as the wallbox and Home Energy Management Systems (HEMS)
- Participate in workshops every two months, provide feedback and complete surveys
- Adapt their behaviour as best as possible, according to the project team’s guidance

3.2.3

Individual visits

Interested participants were invited to schedule individual home visits in November 2023. These visits, conducted with an energy consultant from Klima-Agence and an external communication expert, aimed to:

- Assess motivation and technical suitability for the project
- Document existing assets and estimate the effort to install wallboxes and a HEMS

Candidates completed a survey on their motivation, willingness to adapt, and availability. The collected data was used to create an evaluation matrix, where survey responses were weighted by priority to assess the benefits and risks for each street

3.2.4

Selection criteria

All four streets demonstrated strong motivation. Ultimately, 14 households in Cruchten were selected based on:

- High interest in the energy transition and commitment to serve as role models for their communities
- Willingness to adapt behaviour for the test phases
- Diversity of household types and a strong sense of community spirit

4

Participants' technical installations

This chapter provides an overview of the technical installations implemented in the Creos Living Lab. The objective was to reach a target configuration which replicates the vision of the “2030 household” projected in the NECP.

During the first half of 2024, internal project preparations were made. This included tenders for the technical material, as well as internal IT developments.




Table 2
Timeline of the phases linked to participants' technical installations

The installation of the wallboxes and batteries was made in June 2024, right before the project launched in July. From July to October, the technical installations as well as the HEMS were stabilized.

4.1

Target configuration

The target configuration of project participants is composed of the following assets (Figure 5):

- An EV with a wallbox
- A heat pump
- A PV installation
- A Home Energy Management System (HEMS)

Some installations slightly vary from the target configuration:

- Four participants are equipped with a battery
- Three participants do not have a PV installation
- Two participants do not have a heat pump




Figure 5
Visual representation of the target configuration of assets installed at participants' homes

4.3.2

Home Energy Management System

The objective of the HEMS is to optimize the usage of electricity by visualizing the participants’ data and by automizing the use of certain devices.

The HEMS gathers data from different appliances to show the user which devices are consuming or producing in their household. This helps to raise awareness on their consumption habits. Moreover, it can steer the wallbox and the battery.




Figure 7
Example of the HEMS application showing the electricity consumption and production

5

Smart Grid

